

## For NASA Webb telescope engineers, COCOA this winter means precision testing

December 15 2011

---



The Center Of Curvature Optical Assembly (COCOA) will allow the program to verify the optical performance of the 21.3-foot (6.5-meter) primary mirror at its 40 degrees Kelvin (-233 Celsius) operating temperature. The COCOA contains mechanical and optical instruments that allow the test team to identify, align and test the 18-segments from outside the vacuum chamber. Credit: Note: The background of this image has been digitally removed. Credit: ITT Exelis

Engineers working on NASA's James Webb Space Telescope are bringing out the COCOA this winter, but it's not a warm beverage. Rather, it's a way to check that the mirrors are perfectly shaped and will work in the frosty environment of space.

COCOA stands for "Center of Curvature Optical Assembly." Curvature is important in a mirror, just as the convex side [mirrors](#) on your car are shaped to give you a wide field of vision behind and beside your car. COCOA tests on the Webb telescope's concave mirror segments are critical because they will tell engineers if all of the mirrors work together to make a [telescope](#) that has the correct shape.

"We need to check that the mirrors are of the right prescription, just like eyeglasses, so the images from our telescope are not blurry," said Lee Feinberg, Webb telescope [Optical Telescope](#) Manager at NASA's Goddard Space Flight Center, Greenbelt, Md.

The Webb telescope has 21 mirrors, with 18 of these being six-sided segments working together as one large 21.3-foot (6.5-meter) mirror. Every individual mirror has been previously tested to confirm it has the correct shape, but testing them all together as an assembled telescope with COCOA ensures that the telescope as a whole works correctly.

The COCOA is part of NASA's vacuum cryo equipment that will be used at NASA's Johnson Space Center in Houston to test the performance of the mirrors at operating temperatures. That's important because COCOA tells engineers if the full 18 segment mirror is functioning correctly in "operating temperatures" of 40 degrees Kelvin (-233 Celsius, or -387.4 Fahrenheit) prior to final assembly of the observatory before launch.

[COCOA](#) was built by ITT Exelis of Rochester, N.Y., with subcontractor Micro Instruments in Rochester, N.Y. ITT Exelis and Micro Instruments engineers are assembling the large Center of Curvature test system.

Provided by NASA's Goddard Space Flight Center

Citation: For NASA Webb telescope engineers, COCOA this winter means precision testing (2011, December 15) retrieved 29 May 2023 from <https://phys.org/news/2011-12-nasa-webb-telescope-cocoa-winter.html>

This document is subject to copyright. Apart from any fair dealing for the purpose of private study or research, no part may be reproduced without the written permission. The content is provided for information purposes only.